



ENGINEERING CELL
Delhi Technological University
Shahbad Daulatpur, Bawana Road, Delhi-110042

File No: DTU/Engg.Cell/3259/2021-22/Civil

Dated: 12.07.2022

NOTICE INVITING QUOTATION


The Chief Project Officer, Engineering Cell, DTU invites, on behalf of Delhi Technological University, sealed percentage rate quotations from Civil Contractors up to 03.00 PM on 22.07.2022 for the following works, which shall be opened at 03:30 PM on the same day. Schedule of work along with terms and conditions can be obtained from office of the Chief Project Officer/DTU or DTU website on all working days by submitting an application along with a copy of G.S.T. No. or PAN Card up to 02:00 PM on 22.07.2022.

S. No.	Name of Work	Estimated Cost (Rs.)	Time Allowed	Last date of Receipt of Quotation
1.	Repair and renovation of i.e. balcony covering work, floor tile work in entire flat and wooden work in kitchen and drawing room in Type-5/49 at Residential Block, DTU campus.	4,92,234/-	30 days	22.07.2022

TERMS & CONDITIONS:-


1. The work shall be carried out as per CPWD specifications/manufacturer's specification.
2. The rates quoted should be inclusive of all the taxes and duties & nothing extra shall be paid.
3. The quotations which are issued from the office of CPO shall only be accepted, quotations in other forms shall be summarily rejected without assigning any reasons.
4. No T&P shall be issued to the firm by the department.

Enclosure: Schedule of work.


(Prof. Amit Shrivastava)
Chief Project Officer
DTU Campus, Bawana Road

Copy to: -

1. Registrar, DTU
2. Sr. Account Officer, DTU
3. A E.(Civil)/J.E. (Civil)
4. Notice Board


(Er. Mohit Tyagi)
A.E. (Civil), DTU

Schedule of Work

Name of Work:- Repair and renovation of i.e. balcony covering work, floor tile work in entire flat and wooden work in kitchen and drawing room in Type-5/49 at Residential Block, DTU campus.

S.No.	Description of items	Qty	Unit	Rate	Amount
1	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on Nitco make ceramic tile adhesive @ 3.3kg/sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm	190.00	Sqm	1119.40	212686.00
2	Hacking of CC flooring including cleaning for surface etc. complete as per direction of the Engineer-in-Charge.	190.00	Sqm	1.50	285.00
				Total	212971.00
				Add Cost Index 34.96 % on DSR-2016	74454.66
				Total	287425.66
				Less on 9.50% on DSR-2016	-27305.44
				Total (A)	260120.22
	Non DSR Items				
3	Aluminium partition work in balcony duly made of Powder coated aluminium (minimum thickness of powder coating 50 micron) with float glass panes of 5.50 mm thickness and anodised aluminium grill (anodised transparent or dyed to required shade according to IS: 1868 with minimum anodic coating of grade AC 15) of approved design/pattern, with approved standard section of approved size including fittings and fixtures in balcony area all complete as per direction of Engineer-in-charge.	279.33	Sq.ft	582.00	162570.06
4	Providing and fixing box type wooden wardrobe/Almirah duly made with pressed ply board of 18mm thickness with 2 mm thick laminated sheet on both side including all fittings i.e. 300 mm dia handle, lock, 200 mm dia tower bolt etc. as per approved design and drawings including fixing of fixture and fitting all complete as per direction of Engineer-In-charge. (Minimum depth of almirah is 600 mm). <i>Plan area shall be measured for payment purpose.</i>	6.50	Sq.mt	10699.10	69544.15
				Total (B)	232114.21
				Total (A+B)	492234.43

Note:-

1. All samples must get approved from Engineer-in-Charge before statring the work.
2. All works includes rapairing of wall where the section and almirah fixed as per satisfaction of Engineer-in-Charge. Nothing shall be paid extra on any account
3. Conractor are advised to visit the site before quoting the rate. Nothing shall be extra on any account.
4. Floor Tile make:- Orient Bell, Kajaria, Rak)


(Civil)


A.E. (Civil)


CPO/DTU