



ENGINEERING CELL
Delhi Technological University
Shahbad Daulatpur, Bawana Road, Delhi-110042

File No: DTU/Engg.Cell/3407/2022/Civil

Dated: 28.09.2022

NOTICE INVITING QUOTATION

The Chief Project Officer, Engineering Cell, DTU invites, on behalf of Delhi Technological University, sealed percentage rate quotations from Civil Contractors up to 03.00 PM on 06.10.2022 for the following works, which shall be opened at 03:30 PM on the same day. Schedule of work along with terms and conditions can be obtained from office of the Chief Project Officer/DTU or DTU website on all working days by submitting an application along with a copy of G.S.T. No. or PAN Card up to 02:00 PM on 06.10.2022.

S. No.	Name of Work	Estimated Cost (Rs.)	Time Allowed	Last date of Receipt of Quotation
1.	Special Repair and renovation work i.e. floor tiling work and white washing work in Type-V/22 at Residential Block, DTU campus.	3,42,374/-	20 days	06.10.2022


TERMS & CONDITIONS:-


1. The work shall be carried out as per CPWD specifications and as per direction of Engineer-in-Charge.
2. The rates quoted should be inclusive of all the taxes and duties & nothing extra shall be paid.
3. The quotations which are issued from the office of CPO shall only be accepted, quotations in other forms shall be summarily rejected without assigning any reasons.
4. No T&P shall be issued to the firm by the department.
5. Necessary recoveries shall be made from the bill.

Enclosure: Schedule of work.

Copy to: -

1. Registrar, DTU
2. Sr. Account Officer, DTU
3. A.E.(Civil)/J.E. (Civil)
4. Notice Board


(Prof. Amit Shrivastava)
Chief Project Officer
DTU Campus, Bawana Road


(Er. Mohit Tyagi)
A.E. (Civil), DTU

of Work:- Special Repair and renovation work i.e. floor tiling work and white washing work in Type-V/22 at I Block, DTU campus.

S.No.	Description of items	Qty	Unit	Rate (Rs.)	Amount (Rs.)
1	Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately). Size of Tile 600x600 mm	139.76	Sqm	1119.40	156447.34
2	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinnable priming coat with cement primer	590.00	Sqm	93.70	55283.00
3	Hacking of CC flooring including cleaning for surface etc. complete as per direction of the Engineer-in-Charge.	139.76	Sqm	1.50	209.64
4	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	590.00	Sqm	87.35	51536.50
5	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	590.00	Sqm	10.80	6372.00
6	French spirit polishing :Two or more coats on new works including a coat of wood filler	50.00	Sqm	209.75	10487.50
				Total	280335.98
				Add Cost Index 34.95 % on DSR-2016	97977.43
				Total	378313.41
				Less on 9.50% on DSR-2016	-35939.77
				Total	342373.63
				Say	342374.00


J.E. (Civil)
7/9/22


A.E. (Civil)


CPO/DTU