



**Engineering cell**  
**Delhi Technological University**  
Rohbad Daulatpur, Bawana Road, Delhi-110042

File No: DTU/Engg.Cell/003582/2022-23/Civil/6641

Dated: 16-02-2023

**NOTICE INVITING QUOTATION**


The Chief Project Officer, Engineering Cell DTU invites, on behalf of Delhi Technological University, sealed percentage rate short terms quotations from Civil Contractors up to 3:00 PM on 21/02/2023 for the following works, which shall be opened at 3:30 PM on the same day. Schedule of work along with terms and conditions can be obtained from office of the Chief Project Officer on all working days by submitting an application along with a copy of G.S.T. No. and PAN Card up to 03:00 P.M. on 21/02/2023.

| S. No. | Name of Work   | Estimated Cost (Rs.) | Time Allowed | Last date of Receipt of Quotation |
|--------|--|----------------------|--------------|-----------------------------------|
| 1.     | Supply and fixing of False Ceiling in Class Room No 001 at East Delhi Campus, Vivek Vihar Phase II, Jhilmil Colony, Delhi. | 1,64,657/-           | 05 days      | 21-02-2023 ✓                      |

**TERMS & CONDITIONS:-**


1. The rates quoted should be inclusive of all the taxes and duties & nothing extra shall be paid.
2. The quotations which are issued from the office of Chief Project Officer shall only be accepted. quotations in other forms shall be summarily rejected without assigning any reasons.
3. No T&P shall be issued to the firm by the department.
4. All necessary recoveries shall be recovered from the bill.
5. Schedule of work is completed within 05 days.
6. Payment shall be done after completion of work.

**Enclosure: Schedule of work.**

  
16/2/23  
**Chief Project Officer**  
DTU Campus, Bawana Road  
Delhi

Copy to:-

1. Sr. Account Officer, DTU
2. A.E. (Civil)
3. DTU Website or DTU Notice Board
4. Guard File

  
16/02/2023  
**Assistant Engineer (Civil)**  
DTU Campus, Bawana Road  
Delhi

### SCHEDULE OF WORK

Name of work: Supply and fixing of False Ceiling in Class Room No 001 at East Delhi Campus,  
Vivek Vihar Phase II, Jhilmil Colony, Delhi.

| S. No.                       | Description of Work  | Qty.  | Unit   | Rate    | Amount           |
|------------------------------|--|-------|--------|---------|------------------|
| 1                            | Providing and Fixing 15 mm thick densified tegular edged eco friendly light weight calcium silicate false ceiling tiles of approved texture of size 595 x 595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanised steel sections (galvanising @ 120 grams per sqm including both side) consisting of main 'T' runner suitably spaced at joints to get required length and of size 24x38 mm made from 0.33 mm thick (minimum) sheet, spaced 1200 mm centre to centre, and cross "T" of size 24x28 mm made out of 0.33 mm (Minimum) sheet, 1200 mm long spaced between main 'T' at 600 mm centre to centre to form a grid of 1200x600 mm and secondary cross 'T' of length 600 mm and size 24 x28 mm made of 0.33 mm thick (Minimum) sheet to be inter locked at middle of the 1200x 600 mm panel to form grid of size 600x600 mm, resting on periphery walls partitions on a Perimeter wall angle pre-coated steel of size(24x24X3000 mm made of 0.40 mm thick (minimum) sheet with the help of rawl plugs at 450 mm centre to centre with 25 mm long dry wall screws @ 230 mm interval and laying 15 mm thick densified edges calicum silicate ceiling tiles of approved texture in the grid, including, cutting/ making opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. | 90.00 | Sq.mtr | 1829.52 | 164657.00        |
| <b>Total Amount (in Rs.)</b> |  |       |        |         | <b>164657.00</b> |

*Anwar*  
16/2/23  
Chief Project Officer (DTU)

*Ruqaita Ay*  
16/02/2023  
Assistant Engineer (Civil)

*Sumit*  
16/02/2023  
Junior Engineer (E)