



ENGINEERING CELL
Delhi Technological University
Shahbad Daultapur, Bawana Road, Delhi-110042

File No: DTU/Engg.Cell/0031/2023-24/Civil

Dated: 08.06.2023

NOTICE INVITING QUOTATION

The Chief Project Officer, Engineering Cell, DTU invites, on behalf of Delhi Technological University, sealed percentage rate quotations from Civil Contractors up to 03.00 PM on 19.06.2023 for the following works, which shall be opened at 03:30 PM on the same day. Schedule of work along with terms and conditions can be obtained from office of the Chief Project Officer/DTU or DTU website on all working days by submitting an application along with a copy of G.S.T. No. or PAN Card up to 02:00 PM on 19.06.2023.

S. No.	Name of Work	Estimated Cost (Rs.)	Time Allowed	Last date of Receipt of Quotation
1.	Routine white washing and painting work and other allied civil work in Residential Flats at DTU main campus.	4,85,102/-	15 days	<u>19</u> .06.2023

TERMS & CONDITIONS:-


1. The work shall be carried out as per CPWD specifications/manufacturer's specification.
2. The rates quoted should be inclusive of all the taxes and duties & nothing extra shall be paid.
3. The quotations which are issued from the office of CPO shall only be accepted, quotations in other forms shall be summarily rejected without assigning any reasons.
4. No T&P shall be issued to the firm by the department.

Enclosure: Schedule of work.


2/6/23
Chief Project Officer
DTU Campus, Bawana Road

Copy to: -

1. Registrar, DTU
2. Sr. Account Officer, DTU
3. A.E.(Civil)/J.E. (Civil)
4. Notice Board


02/06/2023
A.E. (Civil), DTU

Schedule of Work

Name of Work:- Routine white washing and painting work and other allied civil work in Residential Flats at DTU main campus.


S.No.	DSR Code	Description of items	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
1	14.46	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	1480.00	Sqmt.	10.80	15984.00
2	13.80	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	1480.00	Sqmt.	87.35	129278.00
3	13.41.1	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinnable priming coat with cement primer.	1480.00	Sqmt.	93.70	138676.00
4	13.61.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	214.78	Sqmt.	12.24	2628.91
5	13.68.1	French spirit polishing : Two or more coats on new works including a coat of wood filler	190.52	Sqmt.	209.75	39961.57
6	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	60.00	Cum	120.55	7233.00
7	14.75	Repair to plaster of thickness 12mm to 20 mm in patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete as per the direction of Engineer-In- Charge.	50.00	Sqm	368.90	18445.00



8	8.2.2.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite of any colour and shade. Area of slab over 0.50 sqm	1.73	Sqm	3113.30	5386.01
9	8.5	Extra for providing opening of required size & shape for wash basin/ kitchen sink in kitchen platform, vanity counter and similar location in marble/ Granite/ stone work, including necessary holes for pillar taps etc. including moulding, rubbing and polishing of cut edges etc. complete.	1.00	Each	427.95	427.95
10	18.9.8	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 75 mm nominal inner dia Pipes	4.00	Mtr	1201.05	4804.20
11	18.9.9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 100 mm nominal inner dia Pipes	2.00	Mtr	1618.10	3236.20
12	14.85	Taking out existing wooden door shutter, repair by cutting, painting etc. and refixing of repaired door shutters to existing door frames, including replacement of hinges with screws, etc. as required, all complete as per the direction of the Engineer-in-charge.	13.00	Each	176.40	2293.20
						368354.04
Add 31.27% Cost Index on DSR Items						115184.31
Total						483538.34
Less 9.50% as per circular						-45936.14
Total (A)						437602.20

Non Schedule Items						
13	NSR	Fixing of English sheet after removing of Indian sheet including demolish of 3" PCC floor with this and jointing of plumber work with material of nani trip, 4" to 3" reducer tee, 4" half set, bend, m seal and solvent etc including plumber and labour charge with 3" PCC through mason work all are finish as per direction of Engineer-in-Charge.	2	Each	8000.00	16000.00
14	NSR	Sewer line cleaning through jet and sucking machine in hostel area & main line in DTU campus as per direction of Engineer in Charge.	1	Job work	31500.00	31500.00
					Total (B)	47500.00
					Total (A+B)	485102.20


JEC


 AB

111
 47