



566

DELHI TECHNOLOGICAL UNIVERSITY
(Formerly Delhi College of Engineering)
Shahbad Daultpur, Bawana Road, Delhi-110042

File No: DT/DEAN-OEA/MAINTENANCE-LOW/23/72/PUR/01

Dated: 28.08.2025

NOTICE INVITING QUOTATION

The Engineering Cell, DTU invites, on behalf of Delhi Technological University, sealed percentage rate quotations from Civil Contractor up to 03:00 M on 02.09.2025 for the following works, which shall be opened at 03:30 PM on the same day. Schedule of work along with terms and conditions can be obtained from office of the Chief Project Officer/DTU or DTU website on all working days by submitting an application along with a copy of G.S.T. No. or PAN

Card up to 03:00 PM on 02.09.2025.

S.No.	Name of Work	Estimated Cost (Rs.)	Time Allowed	Last date of Receipt of Quotation
1.	Repair and Renovation of Lab on Wheels Bus at DTU Campus.	2,10,040/-	15 days	07.09.2025

TERMS & CONDITIONS: -

1. The work shall be carried out as per CPWD specifications and as per direction of Engineer-in-Charge.
2. The rates quoted should be inclusive of all the taxes and duties & nothing extra shall be paid.
3. No T&P shall be issued to the firm by the department.
4. Penalty on account of delay of the work (if any) may be imposed @1000/- per day or as decided by the Engineer-in-Charge.
5. Labour cess @1% shall be deducted from the bill as per norms/ rules.
6. Necessary recoveries shall be made from the bill.
7. Sample of materials shall be got approved from Engineer-in-Charge before procuring the materials.
8. Time allowed: - 15 Days

Enclosure: Schedule of work.

Anwar

Chief Project Officer

Copy to:-

1. Registrar, DTU
2. Sr. Account Officer, DTU
3. J.E. (Civil/Electrical)
4. DTU website
5. Notice Board

Rojan

Executive Engineer

Schedule of Work

Name of work :- Regarding Repair and renovation of Lab on Wheels Bus at DTU Campus.


S No	Item	Qty.	Unit	Rate Rs.	Amount Rs.
1	Repair and renovation of the Mobile Computer Lab, including removal of external stickers, rust marks, and other surface contaminants. It includes checking and repairing the fabricated body wherever required to prevent water ingress, particularly around the air conditioning units. The external body shall be prepared suitably for painting, followed by the application of 2K paint in the existing shade. The scope also includes replacement of 18 existing switches and sockets with modular plate type fittings, checking and repairing or replacing the wiring harness as necessary, and replacement of the external power supply cable along with the installation of a manually operated cable drum in place of the existing self-recoiling type. Further, the job includes complete servicing of the genset, two split-type air conditioning units, and a 6 KVA UPS with associated batteries. The final step includes branding through vinyl stickers as per the existing design and matter or as directed by the Engineer-in-Charge.	1	Per Job	210040	210040
Total					210040

Terms and conditions :-

1. The work shall be carried out as per entire satisfaction of the Engineer in charge.
2. Quoted rates shall be inclusive of all taxes applicable and cartage etc.
3. No T & P shall be issued to the contractor by the department.
4. All safety measure shall be taken while execution of work.
5. Time period for execution of work is 07 day.


JE(Civil)


JE(Elect.)


PO (Elect.)


Chief Project Officer