



Engineering Cell
DELHI TECHNOLOGICAL UNIVER
(Formerly Delhi College of Engineering)
Shahbad Daultapur, Main Bawana Road, Delhi-42

विकसित भारत
अभियान
1947 - 2047

File No: DTU/Engg.Cell/00177/2024-25/Civil

Dated: 11.11.2024

NOTICE INVITING QUOTATION

The Chief Project Officer, Engineering Cell, DTU invites, on behalf of Delhi Technological University, sealed percentage rate quotations from Civil Contractor up to 11:00 AM on 14.11.2024 for the following works, which shall be opened at 11:30 AM on the same day. Schedule of work along with terms and conditions can be obtained from office of the Chief Project Officer/DTU or DTU website on all working days by submitting an application along with a copy of G.S.T. No. or PAN Card up to 11:00 AM on 14.11.2024.

S.No.	Name of Work	Estimated Cost (Rs.)	Time Allowed	Last date of Receipt of Quotation
1.	Providing and fixing of bamboo fencing and supply of ashok pendula for main gate boundary wall gate no. 2 to Parking area of wall at DTU Campus.	4,59,686/-	8 days	14.11.2024

TERMS & CONDITIONS:-

1. The work shall be carried out as per CPWD specifications/manufacturer's specification.
2. The rates quoted should be inclusive of all the fuel taxes and duties & nothing extra shall be paid.
3. The quotations which are issued from the office of CPO shall only be accepted, quotations in other forms shall be summarily rejected without assigning any reasons.
4. No T&P shall be issued to the firm by the department.
5. All rates are including of GST.

Enclosure: Schedule of work.

Royan
11/11/2024

Executive Engineer
DTU Campus, Bawana Road
Delhi

Copy to:-

1. Registrar, DTU
2. Sr. Account Officer, DTU
3. J.E. (Civil)
4. DTU website
5. Notice Board

AE, Civil (CDC)
11.11.24


Schedule of Quantity


Name of work:- Providing and fixing of bamboo fencing and supply of ashok pendula for main gate boundary wall gate No.2 to Parking area of wall at DTU Campus.


S. No.	DSR Code	Description Of Items	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
1	9.110	Providing and fixing Bamboo jaffery/ fencing consisting of superior quality 25mm dia (Average) half cut bamboo placed vertically and fixed together with three numbers horizontal running members of hollock wood in scantling of section 50X25 mm, fixed with nails and G.I wire on existing support complete as per direction of Engineer-in-charge.	600.00	Sqm	600.15	360090.00
TOTAL						360090.00
Add applicable rate of GST @18% in place of 12% (Multiplying factor 1.0633) on						₹ 3,82,884
Add Cost Index 7%						₹ 26,801.86
Total Rs.						₹ 4,09,686.00 (A)

DSR-Horticulture

2	7.77	Providing and stacking of Polyalthia pendula (Ashok Pendula) of height 180-195 cm. in gunny bag of size 30 cm as per direction of the officer-in-charge.	500.00	Each	100.00	50000.00
TOTAL						50000 (B)
GRAND TOTAL						₹ 4,59,686


J.E. (Civil)


A.E. (Civil) 09.11.24


Executive Engineer, DTU